

Statement of Work

Date: January 19, 2022

Job Type: Installation of CCTV System at Wattala Warehouse

Job Description:

CCTV System requirement & installation instructions:

1. Contractor is responsible to obtain all necessary details/ measurement to install the CCTV System.
2. Contractor should supply and install the following:
 - a. 3MP IP IR Bullet cameras- 22 numbers
 - b. 44 channel IP NVR- 2 numbers
 - c. PoE switch -1 number
 - d. LED 32" CCTV monitors – 3 numbers
 - e. 7U equipment Rack- 2 numbers
 - f. 2KVA offline UPS – 2 numbers
 - g. Surge Protectors – 22 sets
 - h. 4"x 15' GI CCTV pole -1 number.
 - i. 3 to 4 ft extended camera arms – 5 numbers
3. All camera cables must come directly to the recording NVR first and then distribute to the front Security Booth NVR (for spot monitor selection).
4. NVRs should be powered through the UPS.
5. Guard room shall be equipped with 2 monitors with one being a spot monitor, and the other being a multi screen monitor. A separate NVR to control the spot monitor shall be included.
6. 1 Monitor shall be installed at the NVR with a multi screen display to be located inside the Safe Room.
7. Contractor shall use PVC casing/conduit for surface wiring and GI rigid conduit for underground wiring.
8. Contractor shall provide a two years 100% warranty on the complete system and should respond immediately in case of a breakdown.
 - a. If the system break or stops working during the warranty period the Contractor shall provide either immediate replacement parts at no cost to the Embassy or provide a loaner device until the broken device is repaired.
 - b. No hard drives can be released from the Embassy compound if they have ever recorded video at the compound without Embassy Security Office approval.

Contractor Obligations

- Construction shall abide by all the Embassy rules and regulations including security and safety regulations.
- The contractor must provide continuous progress on the job site and complete the installation in three weeks.
- The contractor shall provide qualified supervisory, technical, and labor personnel capable of meeting the embassy requirements. The labor force shall possess the masonry, fabrication, metal fitting, painting, and electric/electronic control skills for this project and sufficient staff to accomplish the work in a timely manner.
- Contractor will supply all necessary tools, cables, conduit, mounting brackets, screws and other necessary materials and supplies required for this installation.
- Contractor will carry out work without any physical or equipment support from the embassy.
- Contractor should ensure the minimum disturbance and no damages to the existing property of the premises and inside the building.
- The contractor shall clean up left over materials from the site(s) prior to the project's being determined as complete. No trash or construction debris shall be left in the project area prior to acceptance by the Embassy.

Questions concerning this Scope of Work should be directed to:

Dinusha Sathkumara (E-mail: sathkumaradm@state.gov; Telephone: 0777-709-591)

(Contractors are well come to propose alternative solutions with latest models and should include brand names and specifications of all equipment's.)

Basic Sketch of Equipment locations

